



Northern Town of La Ronge
Box 5680 1212 Hildebrand Drive
La Ronge, Saskatchewan S0J 1L0

REQUEST FOR QUOTE

TOWN OF LA RONGE
Build and Install New Dock and Ramps
at the La Ronge Airport Back Bay

RFQ # 2020-10
August 25th, 2020



ACKNOWLEDGEMENT

The Town of La Ronge hereby requests quotes for the building and installation of a new Dock and Ramps for the La Ronge Airport Back Bay, in accordance with this quote package.

Please submit your quote to:

By mail:

Town of La Ronge / Airport
Po Box 5680
1212 Hildebrand Drive
La Ronge, Saskatchewan S0J 1L0
Attn: Jim Burr, Airport Manager

By fax:

Town of La Ronge / Airport
Attn: Jim Burr, Airport Manager
306-425-4885

By Email:

Jim Burr
airport.manager@laronge.ca

All quotes must be received prior to 4:00 p.m. on Friday, September 18th, 2020.

The Contractor shall be prepared to complete the building of the new Dock, Ramps, Anchors and deliver with all associated hardware to the La Ronge Airport by November 30th, 2020.

The Contractor shall be prepared to remove and dispose of the existing Dock, Anchors and associated hardware as soon as the spring break up allows.

The Contractor shall be prepared to complete the installation of the new Dock, Ramps, Anchors and associated hardware at the La Ronge Airport Back Bay as soon as the spring break up allows.

Late quotes will be rejected.

The Town reserves the right to reject any or all quotes. The lowest quote shall not necessarily be awarded.



CONTRATOR ACKNOWLEDGEMENT

"We hereby offer to supply all goods and/or services necessary for the proper and expeditious completion of the Agreements in accordance with the specifications and any other requirements as quoted"

"We agree to comply with the terms and conditions herein and to commence the work immediately when authorized to proceed and to carry it forward in such a manner as to ensure proper completion at the earliest possible date."

By your signature hereunder, it is deemed that you have read and agreed to all requirements set out in this quote document. Award of this project shall be indicated by the Town of La Ronge by motion of Council. The bidder acknowledges that upon such issuance the bidder shall be bound by the terms and conditions set out herein.

Business Name	Authorized Signature
Address	Name and Title (Please Print)
City/Town Postal Code	Phone Number

SCOPE OF WORK

Description / Scope of the Work -

- Remove and dispose of the existing dock, anchors and associated hardware.
- Build new Dock, Ramps, Anchors and provide associate hardware and deliver to the La Ronge Airport.
- Install the new Dock, Ramps, Anchors and associated hardware at the La Ronge Airport Back Bay.

The Work includes but is not limited to the following:

- a) Mobilization, demobilization, site safety, administration, site clean-up, warranties, general requirements.
- b) All material, labour and equipment required to complete the work is to be provided by the Contractor.
- c) Any damage that may occur during construction is to be repaired by the Contractor to match the pre-existing condition.
- d) The contractor is responsible for all disposal/landfill fees.
- e) The contractor must carry adequate insurance and has the sole responsibility to perform the work in a safe manner in compliance with all safety regulatory requirements.



f) The contractor is responsible for acquiring a business license with the Town of La Ronge. For this project building permits are the responsibility of the Town of La Ronge.

g) The Contractor shall be deemed the prime contractor once the project is awarded. Duties of a prime contractor: <https://www.saskatchewan.ca/business/safety-in-the-workplace/rights-and-responsibilities-in-the-workplace/duties-of-prime-contractors>

Project Specifications

2 Dock Sections to be joined end to end:

- Each section 16' L x 8' W
- Treated material ACQ all-weather 2"x10" framing and 2"x6" decking
- Rodent Resistant Styrofoam Billets Floats
- Heavy Duty Galvanized hardware -corner braces at each corner – adjustable chain braces at each anchor point
- Pivoting hinge connectors between sections

2 Ramp Sections to be joined end to end:

- Each section 16' L x 8' W
- Treated material ACQ all-weather 2"x10" framing and 2"x6" decking
- Rodent Resistant Styrofoam Billets Floats at end that joins the dock
- Heavy Duty Galvanized hardware -corner braces at each corner – adjustable chain braces at each anchor point
- Pivoting hinge connectors between sections

Anchors:

- For Dock Sections – Two 800 lbs concrete anchors per section – Connected with grade 70 3/8" chain and grade 8 bolts
- For Ramp Sections - First section is to be anchored to cement anchors at the shoreline – Second section anchored by two 800 lbs concrete anchors - Connected with grade 70 3/8" chain and grade 8 bolts

These project specifications are preferred. Other floating dock systems may be considered.

COST BASIS

The Contractor shall provide a quote in two parts:

1. The building of the new Dock, Ramps, Anchors and associated hardware and delivery to the La Ronge Airport for winter storage shall be a fixed price. Travel, per diem, taxes and other miscellaneous costs must be included in this price.

2. Removal of the Old Dock, anchors and associated hardware and the installation of the new Dock, Ramps, Anchors and associated hardware in the spring of 2021 shall be a fixed price. Travel, per diem, and other miscellaneous costs must be included in this price.

Direct Questions regarding this RFQ to:

Jim Burr
airport.manager@laronge.ca
306-425-6992



Drawings/Photographs for Reference

